



FOR AUTHORIZED USE ONLY

**SHRI GURU GOBIND SINGHJI
INSTITUTE OF ENGINEERING & TECHNOLOGY,**

VISHNUPURI, NANDED – 431 606

Quotation Notice & Quotation

For

“Making barbed wire fencing over compound wall behind boys hostel.”



**SHRI GURU GOBIND SINGHJI INSTITUTE OF ENGINEERING
& TECHNOLOGY, VISHNUPURI, NANDED-431 606.**

Date: - 28/11/2022

SHORT NOTICE FOR CONTRACTORS

Sealed quotations are invited for **Making barbed wire fencing over compound wall behind boys hostel.** The prescribed format of this work is available our institute web site <https://sggs.ac.in/tenders-site-section/>, from **01/12/2022** to **06/12/2022**. The interested Govt. registered civil contractors/Agencies are requested to give their quotations for above mentioned work up to **06/12/2022 before 01.30 p.m.** If possible, the quotations will be opened at **3.00 p.m.** on the same day or next working day in the presence of contractor who will be remaining present.

The rights are reserved to accept or reject any or all quotation without any notice.

The contractors/Agencies should attach the following documents with Quotation :-

1. The contractor/Agencies should attach with quotation the Registration copy of contractor with any of these Government Department PWD, CPWD, BSNL, MJP.
2. Certificate of GST No.

In the absence of above any documents quotation stand cancelled.


Site Engineer


Secretary
Building & Construction Committee

Copy to the:

- 01 All Notice Boards in this Institute.
- 02 Concerned file No.28
- 03 Institute web site.

Name of Contractor:- _____



**SHRI GURU GOBIND SINGHJI INSTITUTE OF ENGINEERING &
TECHNOLOGY, VISHNUPURI, NANDED-431 606.**

QUOTATION

Name of the Work :- Making barbed wire fencing over compound wall behind boys hostel

Item No.	Name of work	Qty.	Unit	Rate per unit	Total Amount
Item No.1	Dismantling stone masonry in lime or cement mortar including stacking the materials as directed with all leads, lifts etc.	1.63	CU.M		
Item No.2	Providing and laying Cast in situ /Ready Mix cement concrete in M15 of trap/ granite/ quartzite/ gneiss metal for foundation/ steps including steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honey combed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honey combed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic microprocessor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	1.63	CU.M		
Item No.3	Providing and fixing six cross razor horizontal R.B.T. reinforced barbed wire , stud tied with G.I. staples and G.I. clips to retain horizontal including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer with reinforced barbed tape (R.B.T.) / spring core (2.5 mm thick) wire of high tensile strength of 165 kg/ sq.mm. with tape (0.52 mm thick) and weight 43.478 gm/ meter.	67.00	Rg.M		
Item No.4	Providing and fabricating structural steel work in rolled sections like joists, channels, angles, tees etc. as per detailed design and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted/ bolted/ welded connections without connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade for 'Y' frame with six holes etc. complete.	106.31	Kg		
Total Amount :-					

(Rate should be inclusive of GST)*

(Inwards

)

Place:-

Date:-

Sign. Of Contractor/Agency
with seal

Barbed wire fencing over compound wall



