



FOR AUTHORIZED USE ONLY

**SHRI GURU GOBIND SINGHJI
INSTITUTE OF ENGINEERING & TECHNOLOGY,**

VISHNUPURI, NANDED – 431 606

Quotation Notice & Quotation

For

“Replacing damaged flooring in the rooms of Godavari Hostel”



SHRI GURU GOBIND SINGHJI INSTITUTE OF ENGINEERING
& TECHNOLOGY, VISHNUPURI, NANDED-431 606.

Date :- 28/06/2022

SHORT NOTICE FOR CONTRACTORS


Sealed quotations are invited for Replacing damaged flooring in the rooms of Godavari Hostel. The prescribed format of this work is available on our institute web site <https://sggs.ac.in/tenders-site-section/>, from 29/06/2022 to 07/07/2022. The interested Govt. registered civil contractors/Agencies are requested to give their quotations for above mentioned work up to 07/07/2022 before 01.30 p.m. If possible, the quotations will be opened at 3.00 p.m. on the same day or next working day in the presence of contractor who will be remaining present.

The rights are reserved to accept or reject any or all quotation without any notice.

The contractors/Agencies should attach the following documents with Quotation :-

1. The contractor/Agencies should attach with quotation the Registration copy of contractor with any of these Government Department PWD, CPWD, BSNL, MJP, MSSIDC and DIC. OR shop act.
2. Certificate of GST No.

In the absence of above any documents quotation stand cancelled.


Site Engineer




Secretary
Building & Construction Committee

Copy to the :

- 01 All Notice Boards in this Institute.
- 02 Concerned file No. 12
- 03 Institute web site.

Name of Contractor :- _____



SHRI GURU GOBIND SINGHJI INSTITUTE OF ENGINEERING &
TECHNOLOGY, VISHNUPURI, NANDED-431 606.

QUOTATION

Name of the Work :- Replacing damaged flooring in the rooms of Godavari Hostel.

Item No.	Name of work	Qty.	Unit	Rate per Unit	Total Amount
Item No.1	Removing cement tiles, or marble or polished shahabad floor of dado without bed concrete including staking the materials as directed with all leads, lifts etc complete.	28.35	Sq.M.		
Item No.2	Providing & laying matt finish ceramic tiles of having size 30cm x 30cm conforming to IS.15622-2006 (groupDII-A) and 7 to 8 mm thick for flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with white/colour cement slurry cleaning curing etc complete.	28.35	Sq.M.		
Total Amount :-					

(Rate should be inclusive of GST)*

(Inwards _____)

Place :-

Date :-

Sign. of Contractor/Agency
with seal