

FOR AUTHORIZED USE ONLY



**SHRI GURU GOBIND SINGHJI
INSTITUTE OF ENGINEERING & TECHNOLOGY,**

VISHNUPURI, NANDED – 431 606



Quotation Notice & Quotation

For

“Renovation of toilet (WC) of RQ-02 Quarter in institute.”



**SHRI GURU GOBIND SINGHJI INSTITUTE OF ENGINEERING &
TECHNOLOGY, VISHNUPURI, NANDED -431606.**

Date 13.03.2020

SHORT NOTICE FOR CONTRACTORS


Sealed quotations are invited for **Renovation of toilet (WC) of RQ-02 Quarter in institute.** The prescribed format of this work is available institute web site <https://sggs.ac.in/tenders-site-section/>, from **16/03/2020 to 23/03/2020**. The Interested Govt. registered civil contractors /Agencies are requested to give their quotations for above mentioned work up to **23/03/2020** before 01.30 p.m. If possible, the quotations will be opened at **3.00 p.m.** on the same day or next working day in the presence of Contractor who will be remaining present.


The rights are reserved to accept or reject any or all quotation without any notice.

The Contractors/ Agencies should attach the following documents with Quotation:-

1. The contractor should attach with quotation the Registration copy of contractor with any of these Government Department PWD, CPWD, BSNL, MJP, MSSIDC and DIC.
2. Certificate of GST No.

In the absence of above any documents quotation stand cancelled.


Site Engineer


Secretary

Building & Const. Committee

Copy to the:

01. All Notice Boards in this Institute
02. Concerned file 84



**SHRI GURU GOBIND SINGHJI INSTITUTE OF ENGINEERING &
TECHNOLOGY, VISHNUPURI, NANDED - 431606**

Q U O T A T I O N

Name of the work: Renovation of toilet (WC) of RQ-02 Quarter in institute.

Name of Work	Qty.	Unit	Rate	Amount
<u>Item No.1:</u> Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete	1	No.		
<u>Item No.2:</u> Removing W.C. pans including disconnecting the sanitary and water supply connections, removing and breaking flooring and bed concrete around pan removing the same carefully and stacking the serviceable materials as adn where directed including throwing the unserviceable materiasls outside etc. carefully and throwing out the refusal outside etc. complete.	1	No.		
<u>Item No.3:</u> Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete	7.2	Sq.M.		
<u>Item No.4:</u> Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris up to a distance of 50 meters or spreading in the compound and cleaning the site etc. complete.	7.2	Sq.M.		
<u>Item No.5:</u> Removing rich mix cement concrete including stacking the spoils as directed with all leads, lifts etc. complete	0.29	Cu.M.		
<u>Item No.6:</u> Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50m. Beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary backfilling, ramming, watering including shoring and strutting etc. complete. (Lift up to 1.5 m.) By Mechanical Means	1.44	Cu.M.		

<p><u>Item No.7:</u> Conveying Materials obtained from excavation including all lifts, laying in layers, breaking clods, dressing to the required lines, curves, grades and section for a lead of over 300m to 500m inclusive from the site of excavation to the site of deposition etc. complete. As directed by Engineer in charge.</p>	1.73	Cu.M		
<p><u>Item No.8:</u> Providing and filling in the foundation with sand of approved quality including watering, compacting etc. complete. (To be executed with prior approval of Superintending Engineer)</p>	0.58	Cu.M.		
<p><u>Item No.9:</u> Providing and laying Cast in situ/ Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic microprocessor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand/ Crushed sand VSI Grade finely washed etc.)</p>	0.29	Cu.M.		
<p><u>Item No.10:</u> Providing internal cement plaster 20 mm thick in Single coats in cement mortar 1:5 without neeru finish, to concrete, brick surface, in all positions including scaffolding and curing etc. complete</p>	7.20	Sq.M.		
<p><u>Item No.11:</u> Providing and fixing M40 grade thick vibrated pull cast or similar type concrete frame with chamfer conforming to I.S.65241983 having 6mm dia.bars 3Nos. And stirrups @ 250mmc/c and fixing in wall with 6Nos of hold fast of 12mm dia bars 500mm long including primer and oil painting etc, complete) frame size 60 mm x 100 mm .</p>	5.55	Rg.M.		
<p><u>Item No.12:</u> Providing and fixing fiber glass reinforced polyster door shutter 30 mm thick as per IS 14856 (2000) (Reaffirmed 2006) without ventilator including chromium plated fixtures and fastening with chromium plated handles on both sides, etc. complete</p>	1.98	Sq.M.		
<p><u>Item No.13:</u> Providing and laying Antiskid Ceramic tiles of approved quality of size 30 cm x 30 cm and conforming to IS15622-2006 (Group B II A) for antiskid flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with cement slurry cleaning curing etc. complete.</p>	1.44	Sq.M.		

<u>Item No.14:</u> Providing and laying ceramic tiles having size 30 cm. x 45 cm. conforming to corresponding I.S. for dado and skirting in required position with readymade adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white/ colour cement slurry cleaning curing etc. complete.	5.76	Sq.M.		
<u>Item No.15:</u> Providing and fixing 100 mm dia. Stabiliser pipe/ P.V.C. soilvent/ waste pipe and with necessary fixtures and fitting such as bends, tees, single junctions, slotted vent, clamps etc. complete.	3.00	Rg.M.		
<u>Item No.16:</u> Providing and fixing Orissa Pan of size 580 x 445 x 260 mm with approved make flush valve (jaquar make) including trap, C.I.soil and vent pipe upto out side face of wall including 100mm dia. C.I. plug, bend and necessary pipe connection, 1:2:4 brick bat lime concrete bedding, etc complete. As directed by Engineer in charge.	1.00	No.		
<u>Item No.17:</u> Providing and fixing C.P. BIB cock with wall flange of approved make (jaquar make) including necessary sockets/ union nut etc. complete.	1.00	No.		
<u>Item No.18:</u> Providing and fixing on walls/ ceiling/ floor 32 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	3.00	Rg.M.		
<u>Item No.19:</u> Providing and fixing on walls / ceiling / floor 25mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	3.00	Rg.M.		
<u>Item No.20:</u> Providing and fixing on walls/ceiling/floor 20 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	3.00	Rg.M.		
<u>Item No.21:</u> Removing white wash or colour wash by steel wire brushing and / or scrapping by sand paper and preparing the wall surface smooth including necessary repairs to scratches etc. complete. As directed by Engineer in charge	13.44	Sq.M.		

<p><u>Item No.22:</u> Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.</p>	13.44	Sq.M.		
<p><u>Item No.23:</u> Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.</p>	13.44	Sq.M.		
Total Amount				

(Rate should be inclusive of GST)

(In words _____)

Place:-

Date:

Sign. Of Contractor