

FOR AUTHORIZED USE ONLY



**SHRI GURU GOBIND SINGHJI
INSTITUTE OF ENGINEERING & TECHNOLOGY,**

VISHNUPURI, NANDED – 431 606



Quotation Notice & Quotation

For

**“Construction of Brick Masonry and Plastering to the water shed
management training center at Nagdervadi.”**



**SHRI GURU GOBIND SINGHJI INSTITUTE OF ENGINEERING &
TECHNOLOGY, VISHNUPURI, NANDED -431606.**

Date 23.06.2020

SHORT NOTICE FOR CONTRACTORS


Sealed quotations are invited for **Construction of Brick Masonary and Plastering to the water shed management training center at Nagdervadi.** The prescribed format of this work is available institute web site <https://sggs.ac.in/tenders-site-section/>, from **23/06/2020 to 01/07/2020.** The Interested Govt. registered civil contractors /Agencies are requested to give their quotations for above mentioned work up to **01/07/2020** before 01.30 p.m. If possible, the quotations will be opened at **3.00 p.m.** on the same day or next working day in the presence of Contractor who will be remaining present.


The rights are reserved to accept or reject any or all quotation without any notice.

The Contractors/ Agencies should attach the following documents with Quotation:-

1. The contractor should attach with quotation the Registration copy of contractor with any of these Government Department PWD, CPWD, BSNL, MJP, MSSIDC and DIC.
2. Certificate of GST No.

In the absence of above any documents quotation stand cancelled.


Site Engineer


Secretary

Building & Const. Committee

Copy to the:

01. All Notice Boards in this Institute
02. Concerned file 01



**SHRI GURU GOBIND SINGHJI INSTITUTE OF ENGINEERING &
TECHNOLOGY, VISHNUPURI, NANDED - 431606**

Q U O T A T I O N

Name of the work: Construction of Brick Masonry and Plastering to the water shed management training center at Nagdervadi.

Name of Work	Qty.	Unit	Rate	Amount
Item No. 1 Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete	18.40	Cu.M.		
Item No. 2 Providing internal cement plaster 20 mm thick in Single coats in cement mortar 1:5 without neeru finish, to concrete, brick surface, in all positions including scaffolding and curing etc. complete)	282.73	Sq.M.		
Item No. 3 Providing and fixing mild steel grill work for windows, ventilators etc. 20 kg/sq.m. as per drawing including fixtures, necessary welding and painting with one coats of anti-corrosive paint and two coats of oil painting complete.	8.36	Sq.M.		
Item No. 4 Providing and laying Cast in situ/ Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic microprocessor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand/ Crushed sand VSI Grade finely washed etc.)	7.44	Cu.M.		
Total Amount				

(Rate should be inclusive of GST)*

(Inwords)

Place :-

Date:

Sign.of Contractor