

FOR AUTHORIZED USE ONLY



**SHRI GURU GOBIND SINGHJI
INSTITUTE OF ENGINEERING & TECHNOLOGY,**

VISHNUPURI, NANDED – 431 606



Quotation Notice & Quotation

For

**“Removing & refixing aluminium partition & repairing false ceiling
at computer lab. in instrumentation dept.”**



SHRI GURU GOBIND SINGHJI INSTITUTE OF ENGINEERING &
TECHNOLOGY, VISHNUPURI, NANDED -431606.

Date 24.08.2020

SHORT NOTICE FOR CONTRACTORS


Sealed quotations are invited for **Removing & refixing aluminium partition & repairing false ceiling at computer lab. in instrumentation dept.** The prescribed format of this work is available institute web site <https://sggs.ac.in/tenders-site-section/>, from 24/08/2020 to 31/08/2020. The Interested Govt. registered civil contractors /Agencies are requested to give their quotations for above mentioned work up to 31/08/2020 before 01.30 p.m. If possible, the quotations will be opened at **3.00 p.m.** on the same day or next working day in the presence of Contractor who will be remaining present.


The rights are reserved to accept or reject any or all quotation without any notice.

The Contractors/ Agencies should attach the following documents with Quotation:-

1. The contractor should attach with quotation the Registration copy of contractor with any of these Government Department PWD, CPWD, BSNL, MJP, MSSIDC and DIC.
2. Certificate of GST No.

In the absence of above any documents quotation stand cancelled.


Site Engineer


Secretary
Building & Const. Committee

Copy to the:

01. All Notice Boards in this Institute
02. Concerned file 06

Name of Contractor:-_____



**SHRI GURU GOBIND SINGHJI INSTITUTE OF ENGINEERING &
TECHNOLOGY, VISHNUPURI, NANDED - 431606**

QUOTATION

Name of the work: Removing & refixing aluminium partition & repairing false ceiling at computer lab. in instrumentation dept.

Name of Work	Qty.	Unit	Rate	Amount
Item No. 1 Removing of aluminium Partition with frames, Glass including labour charges, scaffolding etc. complete. As directed by Engineer in charge.	19.78	Sq.M.		
Item No. 2 Refixing of aluminium Partition with frames, Glass, bidding, rubber bidding, aluminium glazing, door including labour charges, scaffolding, required necessary fittings etc. complete. As directed by Engineer in charge.	10.40	Sq.M.		
Item No. 3 Providing and fixing of suspended false ceiling with galvanized iron perimeter channel, intermediate channel, tees, galvanized iron hanger ceiling section, necessary clips dry wall screw required including framing , boarding, jointing, finishing, with screws and fastener, placing 600mm x 600mm gypsum plaster board tiles 12mm thick etc. complete.	15.21	Sq.M.		
Total Amount				

(Rate should be inclusive of GST)*

(Inwords)

Place :-

Date:

Sign.of Contractor